

## **INSTALL GUIDE**

COM-IDS(RS)-BM1-[ADS-BM1]-EN

DOCUMENT NUMBER 22041

**REVISION DATE** 

20150430

**FIRMWARE** 

COM-IDS(RS)-BM1-[ADS-BM1]

**HARDWARE** 

ADS-BM1

## **ACCESSORIES**

ADS-USB (REQUIRED) COMPATIBLE RF-KIT (OPTIONAL) DRONE MOBILE DR-2000 (OPTIONAL) **NOTICE** The manufacturer will accept no responsability for any electrical damage resulting from improper installation of this product, be that either damage to the vehicle itself or to the installed device. This device must be installed by a certified technician. Please review the Installation Guide carefully before beginning any work.



## **BEFORE INSTALLATION**

- 1- Connect module to computer
- 2- Login to Weblink account
- 3- Flash firmware to module (module is not preloaded with firmware)
- 4- Use accessories accordingly (accessories are sold separately)



Jalastart.

**PAGE 2 OF 20** DOC.: #22041 • 20150430

		FEATURES																		
	NOTES																			
MAKE	NOTES  I This firmware covers Automatic Transmission (AT) vehicles only.	YEAR	INSTALL TYPE	3X LOCK START/STANDALONE MOD.	SECURE TAKEOVER**	DATA IMMOBILIZER BYPASS	ARM 0EM ALARM	DISARM DEM ALARM	DOOR UNLOCK	PRIORITY UNLOCK	TRUNK/HATCH RELEASE	POWER LIFTGATE	PARKING LIGHT CIRE	TACHOMETER STATUS MONITORING	BRAKE PEDAL STATUS MONITORING	VSS STATUS MONITORING	GLOW PLUG STATUS MONITORING	DOOR STATUS MONITORING	TRUNK STATUS MONITORING	HOOD STATUS MONITORING*
_	1 Series PTS AT	08-13		•	•	•			•	•	•			•	•	•				
	3 Series PTS AT***	06-11		•	•	•	•		•	•	•		•	•	•	•		•	•	•
	3 Series Coupe PTS AT***	07-13		•	•	•	•		•	•	•			•	•	•		•	•	•
	5 Series PTS AT	05-10		•	•	•	•		•	•	•	•	•	•	•	•		•	•	•
	6 Series PTS AT	05-10	) 1	•	•	•	• (		•	•	•	•		•	•	•		•	•	•
	1M PTS AT	11	1	•	•	•	•		•	•	•	•	•	•	•	•		•	•	•
	M3 PTS AT***	08-12	2 1	•	•	•	• (		•	•	•	•	•	•	•	•		•	•	•
	M3 Coupe PTS AT***	08-13	3 1	•	•	•	•		•	•	•	•	•	•	•	•		•	•	•
ВММ	M5 PTS AT	06-10	) 1	•	•	•	• (		•	•	•	•	•	•	•	•		•	•	•
-	M6 PTS AT	06-10	1	•	•	•	•		•	•	•	•	•	•	•	•		•	•	•
	X1 PTS AT***	12-15	5 1	•	•	•	•		•	•	•	•	•	•	•	•		•	•	•
	X5 PTS AT	07-13	3 1	•	•	•	•	•	•	•		• •	•	•	•	•		•	•	•
	X5 Diesel PTS AT	07-13	3 1	•	•	•	•	•	•	•		• •	•	•	•	•	•	•	•	•
	X5 M PTS AT	10-13	3 1	•	•	•	•	•	•	•		• •	•	•	•	•		•	•	•
	X6 PTS AT	08-14	1	•	•	•	•	•	•	•		• •	•	•	•	•		•	•	•
	X6 M PTS AT	10-14	1	•	•	•	•	•	•	•		• •	•	•	•	•		•	•	•
	Z4 PTS AT***	09-15	5 1	•	•	•	•	•	•	•	•	•	•	•	•	•		•	•	•
	Clubman PTS AT***	08-15	5 1	•	•	•	•	•	•	•	•	•	•	•	•	•		•	•	•
	Cooper PTS AT***	07-15	5 1	•	•	•	•	• •	•	•	•	•	•	•	•	•		•	•	•
_	Cooper Convertible PTS AT***	08-15	5 1	•	•	•	•	•	•	•	•	•	•	•	•	•		•	•	•
Σ	Countryman / ALL-4 PTS AT	11-15		•	•	•	•	•	•	•	•	•	•	•	•	•		•	•	•
-	Coupe PTS AT***	12-15		•	•	•	•	•	•	•	•	•	•	•	•	•		•	•	•
	Paceman PTS AT	13-15	5 2	•	•	•	•	• •	•	•	•	•	•	•	•	•		•	•	•
	Roadster PTS AT***	12-15	5 1	•	•	•	•	•	•	•	•	•	•	•	•	•		•	•	•


<sup>\*</sup> If equipped with a factory hood switch.

\*\* If equipped with an electric E-brake and it is activated, vehicle will shudown when a door is opened during RS sequence.

\*\*\* If equipped with the Confort Access System, the door handles will not be functional during RS sequence.


PAGE 3 OF 20








(idalastart








**PAGE 5 0F 20** DOC.: #22041 • 20150430

IMPORTANT	INSTALL VIDEO GALLERY AVAILABLE ONLINE
	<ul> <li>Before installing this product, consult our Install Video Gallery and watch:</li> <li>Vehicle Disassembly Procedure videos</li> <li>Module Connection Procedures videos</li> <li>Module Programming Procedures videos</li> <li>Simply visit our forum and register at</li> <li>http://www.12voltdata.com/forum/viewtopic.php?f=340&amp;t=9683&amp;sid=a61772b486e4584ad6f058b171ffa425</li> </ul>





01



START vehicle. Verify all vehicle functionalities. If the vehicle displays error messages or any malfunction: stop the installation and service the vehicle.

02



Turn ignition to OFF position. Remove keyfob from keyport.

03



Verify all keyfob functionalities (Door Lock, Door Unlock, Trunk Release and Comfort Access System if equipped).

04



Insert the expansion pack into module.

U5



Connect the module to the computer with the WEBLINK cable. Flash the module with the latest firmware then flash the expansion pack.

U6



Connect and secure every connector to the vehicle, as shown in STEP 1 of the WIRING DIAGRAM.

07



WARNING: Any vehicle harness that is disconnected during installation, must be re-connected before performing any system tests. Failure to comply will result in vehicle displaying error messages. An OEM scantool will be required to clear the error messages.

08



START vehicle. Verify all vehicle functionalities.

09



WARNING: If the vehicle displays error messages or any malfunction, stop the installation, verify every connection and if the problem persists, call technical support.

10



Turn ignition to OFF position. Remove keyfob from keyport.

11



Connect and secure every connector to the module, as shown in STEP 2 of the WIRING DIAGRAM.

12



Connect and secure every connector of the expansion cable to the module, as shown in STEP 3 of the WIRING DIAGRAM.

1:



If required, connect an accessory as shown in the COMPATIBLE ACCESSORIES section of the quide.

14



If the vehicle is not equipped with a factory hood switch, install an aftermarket hood switch as shown in STEP 4 of the WIRING DIAGRAM.

15




Put sticker 1 on a clean and visible surface in the engine bay and put sticker 2 under the dashboard near the OBDII connector.

16



Module installation procedure completed.











MAKE	MODEL	YEAR	WIRE	CONNECTOR	COUNECTOR	CONNECTOR	POSITION	WIRE COLOR	POLARITY	LOCATION	COMPONENT	
	Countryman / ALL-4 PTS AT	11-15	12V	X14261	~	51 pin	02	Red/Yellow	(+)	Driver kick panel	~	
			Ground	X14261	~	51 pin	47	Brown or Brown/Black	[-]	Driver kick panel	~	
			CanH	X14261	~	51 pin	46	Orange/Green	(DATA)	Driver kick panel	~	
Z			CanL	X14261	~	51 pin	45	Green	(DATA)	Driver kick panel	~	
Σ	Paceman PTS AT	13-15		12V	X14261	~	51 pin	02	Red/Yellow	(+)	Driver kick panel	~
			Ground	X14261	~	51 pin	47	Brown or Brown/Black	[-]	Driver kick panel	~	
			CanH	X14261	~	51 pin	46	Orange/Green	(DATA)	Driver kick panel	~	
			CanL	X14261	~	51 pin	45	Green	(DATA)	Driver kick panel	~	











LED 1 is solid RED. Insert keyfob 1 into keyport.



Within 10 seconds, LED 1 will flash GREEN once (1x).

03



Remove keyfob 1 from keyport.



LED 1 will turn solid RED. Wait 5 seconds.

05



Insert keyfob 1 into keyport.



Within 10 seconds, LED 1 will flash GREEN rapidly.

07



Remove keyfob 1 from keyport.

08



WARNING: Follow steps 4, 3, 2 as shown in the wiring diagram to disconnect the module from the vehicle.

09



Connect module to computer and proceed with KLON programming.

10



WARNING: Follow steps 2, 3, 4 as shown in the wiring diagram to connect the module to the vehicle.



LED 1 will turn solid RED.



Insert keyfob 1 into keyport.

13

LED 1 will turn solid GREEN for 2 seconds.



Remove keyfob 1 from keyport.

15



Module Programming Procedure completed.









NOTE: In Valet Mode, the Remote starter is not functional. Keyless entry, Lock and Unlock will remain functional. See RF kit user manual for alternate valet mode programming.





Insert keyfob into keyport.





Time restriction. Complete next step within 7 seconds.

U.



Cycle ignition ON five times [5x OFF/ON] rapidly. Parking Light will flash once [1x].

04



Wait, Parking Light will flash twice [2x], pause for 1.5 second, then will flash once [1x] to indicate that the valet mode is ON or twice [2x] to indicate that the valet mode is OFF.

05



Turn ignition to STOP position.

06



Remove keyfob from keyport.

07



Valet Mode Programming Procedure completed.

>>



To exit valet mode: repeat steps 1 to 6.



**PAGE 12 OF 20** DOC.: #22041 • 20150430







WARNING: Program aftermarket remotes before usage. A maximum of four [4x] aftermarket remotes per system.





Insert keyfob into keyport.

02



Time restriction. Complete next step within 7 seconds.



Cycle ignition ON five times [5x OFF/ON] rapidly.



Parking Light will flash once [1x].

05



Time restriction. Complete next step within 5 seconds from previous step.



Press once [1x] on LOCK button of aftermarket

07



Parking Light will flash once [1x].

>>



To program additional remotes: repeat steps 5 to 7 using each additional remote.

08



Wait, Parking Light will flash twice [2x].

09



Turn ignition to STOP position.



Remove keyfob from keyport.



Aftermarket Remote Programming Procedure completed.



>>



It is mandatory to exit the Module Navigation at the end of this procedure. Failure to exit the Module Navigation will drain vehicle battery. To exit the Module Navigation at any time: Follow STEP 13.

>>



Module must be programmed to the vehicle.

**>>** 

Use the Module Navigation Chart on the next page.

01



Set ignition to OFF position.

UZ



TO ACCESS THE MENUS: Press and hold programming button until LED 1 turns solid GREEN.

บง



IN THE MENUS: Press the programming button as many times as the menu number indicates. LED 1 will flash GREEN an equal amount of times continuously.

04



TO ACCESS THE OPTIONS: Press and hold programming button until LED 1 turns solid

05



IN THE OPTIONS: Press the programming button as many times as the option number indicates. LED 1 will flash RED an equal amount of times continuously.

06



TO ACCESS THE SETTINGS: Press and hold programming button until LED 1 turns solid GREEN.

07



LED 1 will flash GREEN as many times as the current (or default) setting number, continuously.

80



IN THE SETTINGS: Press the programming button as many times as necessary to access your setting. LED 1 will flash GREEN an equal amount of times continuously.

09



To return to the MENUS: exit the Module Navigation and redo the Module Navigation Procedure.

10



To save and return to the OPTIONS: Press and hold programming button until LED 1 turns solid RED.

11



LED 1 will flash RED as many times as the current option number continuously.

12



Configure every other setting and proceed to step 13.

13



MANDATORY: EXIT MODULE NAVIGATION.
Press and hold programming button for 7
seconds. LED 1 will flash RED rapidly. Release
programming button. LED 1 will turn OFF.

14



Module navigation completed.

>>



Failure to exit the Module Navigation will drain vehicle battery.

**PAGE 14 0F 20** DOC.: #22041 • 20150430



**SETTINGS** [Y] OPTIONS [X] MENUS **MODULE NAVIGATION CHART: NOTES** [Z]I Default settings are listed in bold. 01 0FF 01 DISARM/UNLOCK BEFORE START II Make sure the option is covered on the vehicle before 02 ON attempting to change the setting. 01 **OFF** 02 RELOCK AFTER START 02 ON 01 **OFF** 03 **RELOCK AFTER SHUTDOWN** 02 ON OFF 01 04 FORCE UNLOCK ALL ON FIRST PRESS 02 ON 01 **ENABLE** 05 **TAKEOVER** 02 DISABLE\* 01 **45 SEC** 02 90 SEC 06 SECURE TAKEOVER DELAY 03 03 MIN 04 04 MIN 01 DISABLE 02 N/A 07 FACTORY KEYLESS RS SEQUENCE 03 LOCK + UNLOCK + LOCK CONFIGURATION 04 LOCK + LOCK + LOCK 01 03 MIN 02 05 MIN 03 10 MIN 04 **15 MIN** 08 MODULE RUN TIME 05 25 MIN 06 30 MIN 07 35 MIN **15 MIN** 01 02 SEC 02 05 SEC 03 08 SEC 04 10 SEC WAIT TO START DELAY 09 15 SEC 05 06 20 SEC 25 SEC 07 08 30 SEC 10-15 N/A N/A 01 02-07 Technical Support only 01 N/A 01 N/A

**PAGE 15 OF 20** DOC.: #22041 • 20150430




[X] NUMBER OF PARKING LIGHT FLASHES DIAGNOSTIC **REMOTE STARTER ERROR CODES:** NOTES 01 I WARNING: The following applies only when the parking Engine running. lights are connected and supported by the system. 02 Key in ignition at ON position. II After a remote starter failure, the parking lights will flash 03 N/A three [3x] times, then will flash [X] number times to 04 Trunk is open. indicate an error code. See table. 05 Foot brake is ON. 06 Hood is open. 07 N/A 08 Tach failure. 09 N/A 10 System is in Valet Mode. 11 CAN communication failure RS not synchronized. Start vehicle with OEM key for 15 sec before trying a new RS sequence. 12

REMOTE STARTER SHUTDOWN ERROR CODES: NOTES	[Y] NUMBER OF PARKING LIGHT FLASHES	DIAGNOSTIC
I WARNING: The following applies only when the parking	01	Engine tach signal is lost.
lights are connected and supported by the system.	02	N/A
II If the engine shuts down after a remote starter sequence:  Press and hold the Trunk button and the Start button at the	03	Foot brake is ON.
	04	Hood is open.
same time for 2.5 seconds when using a 1-WAY remote. OR	05	Engine RPM limiter is ON.
Press once [1x] on button "4" when using a 2-WAY remote.	06	Glow plug timeout error.
The parking lights will flash four [4x] times, then will flash	07	Vehicle is moving (VSS).
	08	Check engine warning light is ON.
[Y] number times to indicate an error code. See table.	09	Low fuel warning light is ON.
	10	N/A
	11	CAN communication failure during RS sequence.

PAGE 16 OF 20



	TEST MODULE	LED 1 STATUS	DIAGNOSTIC				
		Flashing RED	Missing/wrong information from firmware or vehicle.				
	DURING PROGRAMMING	Solid RED	Module waiting for more vehicle information.				
1		Flashing GREEN	Additional steps required to complete module programming.				
		Solid GREEN then OFF	Module correctly programmed.				
		OFF	No activity or module already programmed.				
		Flashing RED	Module incorrectly programmed.				
		Solid RED	Module incorrectly programmed.				
П	DURING REMOTE START	Flashing GREEN	Module correctly programmed and operational.				
		Solid GREEN then OFF	Reset in progress.				
		OFF	Invalid ground when running status from remote starter.				
		Flashing RED	Module incorrectly programmed or connected.				
		Solid RED	Missing/wrong information from firmware or vehicle.  Module waiting for more vehicle information.  Module steps required to complete module programming.  Module correctly programmed.  Module incorrectly programmed.  Module incorrectly programmed.  Module incorrectly programmed.  Module correctly programmed and operational.  Messet in progress.  Module incorrectly programmed or connected.  Module incorrectly programmed.  Module incorrectly programmed.  Module incorrectly programmed or connected.  Module incorrectly programmed. Waiting for more vehicle information.  Module not programmed. Waiting for more vehicle information.  Malse ground when running status from remote starter.				
Ш	WITH IGNITION OFF	Flashing GREEN	False ground when running status from remote starter.				
		Solid GREEN then OFF	Reset in progress.				
		OFF	Module at rest and ready for a remote start sequence.				









Disconnect all connectors from module except the BLACK 20-PIN connector.

በ2



Disconnect the BLACK 20-PIN connector.

U3



PRESS AND HOLD programming button while connecting the BLACK 20-PIN connector.

04



Wait, LED 1 will flash RED. RELEASE programming button.

05



LED 1 will turn RED for 2 seconds.

116



Module RESET completed.

07



Reconnect all connectors.

08



Repeat programming procedure.

>>



Failure to follow procedure may result with a DTC or a CHECK ENGINE error message.



**PAGE 18 OF 20** DOC.: #22041 • 20150430





All vehicle doors must be closed and locked prior to remote start sequence.



Time restriction. Complete steps 2 to 5 within 45 seconds.





Unlock driver door.





Open driver door and enter vehicle.



Close driver door.



Press and release BRAKE pedal.





Take over procedure completed.

>>



Failure to follow procedure will result in vehicle engine shutdown.

**PAGE 19 OF 20** DOC.: #22041 • 20150430



	CHECKLIST
01	WARNING: Vehicle engine will start many times. Test in a well ventillated area.
02	Open driver door window for easy vehicle access.
03	Close all vehicle doors, hood and trunk.
04	Press LOCK button three times [3x] rapidly on the OEM keyfob to remote start vehicle.
	QUESTION 1: Does the vehicle remote start?
	YES: Go to step 5.
	NO: The module doesn't detect OEM remote lock button from the vehicle communication network. Check all connection, repeat step 4 and call technical support if the problem persist.
05	Press LOCK button three times [3x] rapidly on the OEM keyfob to shut down vehicle.
	QUESTION 2: Does the vehicle shut down?
	YES: Go to step 6.
	NO: Repeat step 5. If problem persists, push vehicle start button once [1x] to shut down the vehicle and call technical support.
06	Unlock and open driver door.
07	Press LOCK button three times [3x] rapidly on the OEM keyfob to remote start vehicle.
	QUESTION 3: Does the vehicle remote start?
	YES: The module does NOT detect the door signal from the vehicle communication network. Press LOCK button three times [3x] rapidly on the OEM keyfob to shut down vehicle and call technical support.
	NO: Go to step 8.
80	Open hood.
	QUESTION 4: Is the orange warning sticker "Sticker 1" placed under the hood?
	YES: Leave hood open and go to step 9.
	NO: Put the mandatory orange warning sticker "Sticker 1", leave hood open and go to step 9.
09	Close all doors.
10	Press LOCK button three times [3x] rapidly on the OEM keyfob to remote start vehicle.
	QUESTION 5: Does the vehicle remote start?
	YES: Press LOCK button three times [3x] rapidly on the OEM keyfob to shut down vehicle. Go to Question 6.
	NO: Go to step 11.
	QUESTION 6: Is the vehicle equipped with a factory hood switch? (Inside hood latch)
	YES: The module does NOT detect the hood signal from the vehicle communication network. Call technical support.
	NO: Install the mandatory hood switch included in the kit. Repeat installation checklist.
11	Close hood.
12	Enter vehicle. Do NOT press brake pedal.
13	Close all doors.
14	Press LOCK button three times [3x] rapidly on the OEM keyfob to remote start vehicle.
15	Wait for the vehicle to start.
16	Press brake pedal.
	QUESTION 7: Does the vehicle shut down?
	YES: Go to step 17.
	NO: The module does NOT detect the brake pedal signal from the vehicle communication network. Press LOCK button three times [3x] rapidly on the OEM keyfob to shut down vehicle and call technical support.
17	Apply parking brake.
18	Exit vehicle.



PAGE 20 OF 20

DOC.: #22041 • 20150430



Installation checklist completed.

**CHECKLIST** Close all doors. Press LOCK button three times [3x] rapidly on the OEM keyfob to remote start vehicle. 21 Wait for the vehicle to start. **QUESTION 8:** Is the vehicle equipped with Comfort Access System? YES: For 1, 5, 6, X5, X6: Touch exterior driver door handle to unlock door using Comfort Access System. Within 45 seconds, go to step 22. YES: For 3, X1, Z4, Mini: Press UNLOCK button once [1x] on the 0EM keyfob. Within 45 seconds, go to step 22. NO: Press UNLOCK button once [1x] on the OEM keyfob. Within 45 seconds, go to step 22. 22 Open driver door. QUESTION 9: Does the vehicle shut down? YES: For Z4, X5, X6: Go to step 25. YES: For 1, 3, 5, 6, X1: The module does NOT detect the parking brake signal or the unlock signal from the vehicle communication network. Call technical support. NO: For Z4, X5, X6: The module does NOT detect the parking brake signal correctly from the vehicle communication network. Call technical support. NO: For 1, 3, 5, 6, X1: Go to step 23. 23 Press and release brake pedal. 24 Push vehicle start button once [1x] to shut down the vehicle.